

PROOFING CHAMBERS

UMG3 (3-Module Proofing System)

Modular proofing system - 3-module walk-in chamber for large production

TECHNICAL SPECIFICATIONS

Category	Modular Walk-in Proofing Chamber (3-Module Configuration)
Modules	3 interconnected proofing zones
Panel thickness	60 mm
Panel finish	White plastic-coated aluminium RAL 9010
Steam generator	Injection type - 110°C (per module)
Panel system	Modular MULTI - male/female joints, 200 mm modularity
Dimensions	Custom - as per project drawings
Voltage	400 V - Three-phase - 50 Hz
Refrigerant gas	R452A

KEY FEATURES & BENEFITS

- ❑ 3-module: independent temperature/humidity zones for sequential proofing programs
- ❑ Low-maintenance injection steam generator (110°C): 20% less wall condensation vs. traditional steam
- ❑ Modular MULTI panel construction: 60 mm panels, male-female joints, 200 mm modularity
- ❑ White plastic-coated aluminium RAL 9010 standard finish
- ❑ Rounded internal edges for easy cleaning
- ❑ Optional heated floor: eliminates condensation and provides 25-30% energy saving
- ❑ Optional internet connectivity for remote smartphone monitoring
- ❑ Custom dimensions available to fit any production layout

AVAILABLE OPTIONS

- ❑ Heated floor per module
- ❑ Internet connectivity for remote monitoring and control

Contact SITEP S.r.l. for custom configurations, pricing and delivery times.